



Dangisharan Rural Municipality
Office Of Rural Municipal Executive

Hekuli, Dang
Lumbini Province, Nepal

Bill Of Quantities(BOQ)



योजना को नाम : लेटर कुलो लाईनिङ योजना र लेटर अग्रो कन्स्ट्रिक्सन योजना
Location: Dangisharan Rural Municipality-6

SN	Description	Unit	Quantity	Bidder's Rate (In Figures)	Bidder's Rate (In words)	Amount	Remarks
A Civil Works:							
1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications @ Depth upto 3m (mechanical means)	m3	16.75				
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and Packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	4.43				
3	Providing and placing manually mixed M10/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	m3	2.38				
4	Plain cement Concrete (PCC) for RCC works M15 for footings, beam, slab, lintels etc with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site incharge for	m3	9.10				
5	Tor steel or TMT reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction of site incharge.	kg	390.60				
6	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:6 in structure and providing necessary weep holes etc all complete as per Drawing and Technical Specifications	m3	9.94				
7	Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and footings.	m2	100.40				
				Total Cost			
				Vat (13%)			
				Sub Total with VAT			

कर्म बहादुर नेपाली
प्रमुख प्रशासकीय अधिकृत



Dangsharan Rural Municipality
Office Of Rural Municipal Executive
Hekuli, Dang
Lumbini Province, Nepal

Bill Of Quantities(BOQ)

Name Of Project : प्रसङ्गा कुलोमा कन्स्ट्रक्ट निर्माण योजना
Location:- Dangsharan-6



(Signature)

कर्ण बहादुर नेपाली
प्रमुख प्रशासकीय अधिकृत


A	Description	Unit	Quantity	Bidder's Rate (in Rupees)	Maker's Rate (in words)	Amount	Remarks
1	Civil works Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	m3	14.96				
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	3.60				
3	Providing and placing manually mixed M10/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	m3	1.60				
4	Plain cement Concrete (PCC) for RCC works M15 for footing, beam, slab, lintels etc with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site incharge for	m3	8.74				
5	Tor steel or TMT reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction of site incharge.	kg	345.70				
6	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications	m3	14.86				
7	Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and footings.	m2	22.56				
	Total Cost						
	Vat (13%)						
	Sub Total With VAT						



Dangsharan Rural Municipality
Office Of Rural Municipal Executive
Hekuli, Dang
Lumbini Province, Nepal

Bill Of Quantities(BOQ)

Name of Project:- राजपुर शाखा कुलो लाईनिङ योजना र राजपुर कुलो लाईनिङ योजना
Location:- Dangsharan-6, Rajpur



कर्म बहादुर नेपाली
पुस्तक प्रशासकीय अधिकृत


SN	Description	Unit	Quantity	Bidder's Rate (In Figures)	Bidder's Rate (In words)	Amount	Remarks
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm.	36.45				
2	Dismantling work cement mortar masonry wall and disposing of debris materials 10m away in specified place of site as per instruction of site engineer.	m3	15.31				
3	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material as drawings and technical specifications. @ Depth upto 3m (mechanical means)	Cum.	21.97				
4	Providing and laying of hand peck Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum.	6.30				
5	Providing and placing manually mixed M10/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	Cum.	3.15				
6	Plain cement Concrete (PCC) for RCC works M15 with approved quality of cement and sand and stone aggregate including mixing, laying, curing etc all complete as per instruction.	Cum.	23.77				
7	Tor steel or TMT reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction of site incharge.	Kg	1368.53				
8	Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and Footings.	Sqm.	217.16				
			Total Cost				
			Vat (13%)				
			Sub total with VAT				



Dangsharan Rural Municipality
Office Of Rural Municipal Executive
Hekuli, Dang
Lumbini Province, Nepal

Bill Of Quantities(BOQ)

Name of Project:- बागरमाझ कुरो सार्ने र डाँडा कुरो लाईनिङ योजना
Location:- Dangsharan-6



कर्ण बहादुर नेपाली
प्रमुख प्रशासकीय अधिकृत

SN	Description	Unit	Quantity	Bidder's Rate (In Figures)	Bidder's Rate (In words)	Amount	Remarks
A	Civil works						
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm.	83.14				
3	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications @ Depth upto 3m (mechanical means)	Cum.	12.47				
4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum.	7.27				
5	Providing and placing manually mixed M10/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	Cum.	3.64				
6	Plain cement Concrete (PCC) for RCC works M15 with approved quality of cement and sand and stone aggregate including mixing, laying, curing etc all complete as per instruction.	Cum.	15.74				
7	For steel or TMT reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction of site incharge.	Kg	688.04				
8	Providing, Preparing and installing form work including necessary supports and removing after completion for Foundation and footings.	Sqm.	164.56				
		Total Cost					
		Vat (13%)					
		Sub total with VAT					

Dangsharan Rural Municipality,
Office of the RuralMunicipal Executive.

Hekuli, Dang,
Province No.-5, Nepal

BILL OF QUANTITY



[Signature]

कर्ण बहादुर नेपाली
मुख्य प्रशासकीय अधिकृत

Name of project:- Balapur Prahari Dekhi Dakshain Tarla Salaura Jodne Sadak Staronari Dangsharan 5
Type Of the Work:- RCC drain work.

Total Estimated Amount (Without VAT) = Rs.

851,774.02

S.no	Description of works	Unit	Quantity	Contractor's rate (Without VAT)		Total Amount (Rs.)	Remarks
				In figure	In words		
1	E/w excavation in foundation all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the Engineer. (Mechanical Means)	cum	114.56				
2	Providing suitable material and Back filling betli both side of RCC. drain as per drawing and Technical Specifications. (Mechanical Means)	cum	22.91				
3	Providing and laying of hand pack Stone soling on prepared surface as per Drawing and Technical Specifications. (Old Norms)	cum	16.04				
4	Reinforcement bars (Grade 415 or above) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himjal Iron, Panthakarya or equivalent	kg	2,202.14				
5	Providing, Preparing and Installing form work including necessary supports and removing after completion for Foundation and footings. (Class F1 Finish)	sqm	210.03				
6	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications including form works all complete. (2000)	cum	50.41				
Total Civil Work (A) rs.							
Vat13% (B) of A rs.							
Contingency (C)3% of A rs.							
Grand Total (D) A+B+Crs.							

Name of Contractor:-

Address:-

Date:-

Seal:-

Chief administrative officer.