

Dangisharan Rural Municipality.
Office of the Rural Municipal Executive.

Hekuli, Dang.
Lumbini Province Nepal

योजना को नाम : बैबाङ्ग टुस्र देखि दक्षिण तटबन्द निर्माण योजना योजना
ठेगाना :- दंगीशरण गाउँपालिका ४

Bill Of Quantities(BOQ)

Name Of the Place:- ward no. - 4 baibang

SN	Description	Unit	Quantity	Bidder's Rate (In Figures)	Bidder's Rate (In words)	Amount नेपाली	Remarks
A	Civil Works						
1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications.(By Manual Means)	m3	7.20				
2	Providing mechanically woven double twisted crates / mattress (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvaige wire 3.9 mm, lacing wire 2.4 mm) including rolling, cutting and with lacing wire and binding wire as per specification.	m2	193.00				
3	Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.	m3	35.00				
4	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	m3	7.20				
	Estimated Cost						
	Vat (13%)						
	Sub total with VAT						

Name of Contractor:-

Address:-

Date:-

Seal:-



Handwritten signature and initials of the executive officer.

कर्म बहादुर नेपाली
प्रमुख प्रशासकीय अधिकृत

Dangsharan Rural Municipality.
Office of the Rural Municipal Executive.

Hekuli, Dang,
Lumbini Province Nepal

योजना को नाम : सामुदायिक स्वास्थ्य केन्द्र मैली देखि उत्तर जाने बाटो मर्मत योजना
ठेगाना :- दंगीशरण गाउँपालिका ४

Bill Of Quantities(BOQ)

Name Of the Place:- ward no. - 4 mauji

SN	Description	Unit	Quantity	Bidder's Rate (In Figures)	Bidder's Rate (In words)	Amount	Remarks
A	Civil Works						
1	Earth work excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the	m3	217.75				
2	Providing mechanically woven double twisted crates / mattress (Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm) including rolling, cutting and with lacing wire and binding wire as per specification	m2	94.00				
3	Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical	m3	17.00				
4	Providing and laying granular local mix gravel on prepared road surface by mechanical means all complete.	m3	75.60				
	Estimated Cost						
	Vat (13%)						
	Sub total with VAT						

Name of Contractor:-

Address:-

Date:-

Seal:-

गाउँपालिकाको कार्यालय
दंगीशरण, बाटो
मैली, दंगी, नेपाल

प्रमुख प्रशासकीय अधिकारी



Dangisharan Rural Municipality.
Office of the Rural Municipal Executive.

Hekuli, Dang.
Lumbini Province
BOQ

[Signature]
कर्ण बहादुर नेपाली
प्रमुख प्रशासकीय अधिकारी

Name of project :- Butaniya Jhamariya huda Dabari jane Pakki kulo nirman yojana
Name Of the Place:- Dangisharan Ga.pra ward 7
Name Of the Work:- RCC canal works

Estimated Amount without VAT:

171,350.43

S N	DESCRIPTION	UNIT	TOTAL QUANTITY		Rate	AMOUNT	REMARKS
			Fig	Words			
1	of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and	Cum.	53.25				
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications	Cum.	2.70				
3	Providing and placing manually mixed M10/A0 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	Cum.	2.03				
4	Plain cement Concrete (PCC) for RCC works M15 with approved quality of cement and sand and stone aggregate including mixing, laying, curing etc all complete as per instruction.	Cum.	6.30				
5	For steel or MT reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction of site incharge.	kg	467.79				
6	Formwork, shuttering, centering with 25mm thick plank and wooden or steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding net for. (Rate is calculated taking single formwork is used three times)	sqrm	132.00				
			Total Amount:				
			Vat @ 13%				
			Grand total amount (Rs)				

Name of Contractor:-
Address:-
Date:-

Dangisharan Rural Municipality,
Office of the Rural Municipal Executive

Hekuli, Dang,
Lumbini Province

BOQ



(Signature)

कर्ण बहादुर नेपाली
प्रमुख प्रशासकीय अधिकृत

343 973 44

Name of project :- Ward kanyalaya jane Baro dhubai tir pakkhi naha sahd sadak Gravel yojana

Name Of the Place:- Dangisharan Ga pa ward 7

Name Of the Work:- RCC Drain ,box culvert and Graveling

Estimated Amount without VAT:

Rate(Rs)

S N	DESCRIPTION	UNIT	TOTAL QUANTITY		Rate	Words	AMOUNT	REMARKS
			Fig					
1	Drain purpose excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the Engineer.	Cum.	12.80					
2	Providing and laying of hand pack Stone soiling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum.	7.83					
3	Providing and placing manually mixed M10/D40 cement concrete for the foundation and footing etc including compaction, curing, testing and lead 30m. etc. all complete	Cum.	3.52					
4	Plain cement Concrete (PCC) for RCC works M15 with approved quality of cement and sand and stone aggregate including mixing, laying, curing etc all complete as per instruction.	Cum.	13.14					
5	For steel or TMT reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction of site incharge.	kg	799.03					
6	Formwork, shuttering, centering with 25mm thick plank and wooden or steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support is fully unyielding net for. (Rate is calculated taking single formwork is used three times)	sqm	203.43					
7	Providing and laying granular local mix gravel on prepared road surface by mechanical means all complete	Cum.	30.40					
SUB-Total Amount:								
Vat @ 13%								
Grand total amount (Rs)								

Name of Contractor:-

Address:-


Date:-



**Dangisharan Rural Municipality,
Office of the Rural Municipal Executive.**

Hekuli, Dang,
Lumbini Province
BOQ

Estimated Amount without VAT:


कर्ण बहादुर नेपाली
 प्रमुख प्रशासकीय अधिकृत
 Rate (Rs)

Name of project :- Rachhapal Arjuno Gramer Than culvert, Nijhan yojana
 Name Of the Place:- Dangisharan Ga. pa. ward 7
 Name Of the Work:- RCC canal works

SN	DESCRIPTION	UNIT	TOTAL QUANTITY	Rate		AMOUNT	REMARKS
				Fig	Words		
1	Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all fit and leads as per Drawing and Instruction of the Engineer	Cum.	5.50				
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications	Cum.	2.60				
3	Providing and placing manually mixed M20/20 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	Cum.	1.30				
4	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications including form works all complete. (2000)	cum	3.99				
5	Reinforcement bars (Grade 415 or above) work including straightening, clearing, cutting, bending, binding with 20 bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	kg	353.95				
6	Providing, Preparing and installing form work including necessary supports and removing after completion for Foundation and footings. (Class F1 Finish)	sqrm	15.00				
7	Providing, laying and curing Stone masonry works in cement, sand mortar (1:6) finished in perfect lines & level as per specification, drawings & instructions of the site engineer	Cum	6.28				
8	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	30.00				
			Total Amount:				
			Vat @ 13%				
			Grand total amount (Rs)				

Name of Contractor:-
 Address:-
 Date:-

Dangsharan Rural Municipality.

Office of the Rural Municipal Executive.

Hekuli, Dang.

Lumbini Province

BOQ

Estimated Amount without VAT:

Rate(Rs)

361,493.59


Name of project :- Bogati School bhanda tala kuloma wall Tarha culverta Nirman योजना
Name Of the Place:- Dangsharan Ga.pa ward 7
Name Of the Work:- Stone masonry wall

S N	DESCRIPTION	UNIT	TOTAL QUANTITY	Rate		AMOUNT	REMARKS
				Fig	Words		
1	Wall foundation excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterious matter, all lift and leads as per Drawing and Instruction of the Engineer.	cum	4.03				
2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	0.69				
3	Providing and placing manually mixed M10/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete	cum	0.73				
4	Providing, laying and curing stone masonry works in cement, sand mortar (1:6) finished in perfect lines & level as per specification, drawings & instructions of the site engineer.	cum	21.62				
5	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	cum	158.00				
			Total Amount:				
			Vat @ 13%				
			Grand total amount (Rs)				

Name of Contractor:-

Address:-

Date:-


कर्ण बहादुर नेपाल
प्रमुख प्रशासकीय अधिकृत
नेपाली प्रजासत्ताक